



NOTES:

1. WATER PLANT THOROUGHLY WITHIN 2 HOURS OF PLANTING
2. PRUNE DEAD, DAMAGED, OR RUBBING BRANCHES AT THE TIME OF PLANTING. PRUNE THOSE THAT INTERFERE WITH THE SIDEWALK OR STREET AS SPECIFIED. DISPOSE OF PRUNED OR FALLEN BRANCHES AND PLANT MATERIAL OFF SITE.
3. DO NOT FORM UPHILL SAUCER ON 2:1 SLOPES OR GREATER.
4. SCARIFY SIDES AND BOTTOM OF HOLE
5. SET PLANT PLUMB ON UNDISTURBED SOIL OR WELL COMPACTED BACKFILL SOIL.
6. PLACE 3" DEPTH SHREDDED HARDWOOD MULCH IN A CONTINUOUS LAYER. NO MULCH TO BE WITHIN 6" OF STEM.
7. WHEN PLANTING IN GRATES, PAVERS, OR OTHER RESTRICTED AREAS - TREES TO BE CENTERED IN OPENING.
8. STAKING IS OPTIONAL UNLESS REQUIRED BY CITY STAFF. CONTRACTOR RESPONSIBLE TO MAINTAIN TREES IN A PLUMB POSITION THROUGH THE EXTENDED MAINTENANCE PERIOD.

I hereby certify that this plan, specification or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Minnesota

Mark Allen
 Date 3-17-22 Lic. No. 45800

APPROVED 3-19-2022
Paul Kirtz
 CITY ENGINEER

CITY OF ST. PAUL
 DEPARTMENT OF PUBLIC WORKS
 PLANT TREE

Date of Revision
 MARCH 2022

Standard Plate No.
 6000C